

ZULULAMI

LUXURY COASTAL ESTATE

DESIGN CODE

November 2016

Revision 00

CONTENTS

_INTRODUCTION	
Vision	02
_SITE CONSTRAINTS	03
Town planning regulations	
Additional controls	
Site Development Layout	04
_RECOMENDED DESIGN PRINCIPLES	
Summary	05
Of Building - design principles	06
_SUSTAINABILITY	
Energy Efficient Design - SANS XA	08
_AESTHETICS	09
Specific Exclusions	
General Inclusions	
Colour Palette	16
_LANDSCAPING RECOMENDATIONS	
Overview - see Landscape Code	18
_REVIEW SUBMISSION PROCEDURE	
Zululami Panel of Architects	19
List of Approved Architects	20
Rules applicable for Architects	21
Format of Review Submission	22
Review submission fees	23
Local Authority	25
Commencement of Construction	26
SDP - MDR sites	28
_CHECK-LISTS	
Special Residential Sites	
MDR sites	

“BETWEEN NATURE - FOREST, SKY & SEA”

_To create a holistic living environment through the rehabilitation of the surrounds through indigenous landscaping, wetland & forest revival and the promotion of sustainable community living on the North Coast.

The use of natural materials & complimenting colour palettes enhancing the visual uniformity within the sub-tropical landscape.

A “non-architecture” that celebrates spatial experience, openness to nature, maximising views, climate and coastal lifestyle - ultimately developing an architectural expression that is current & local.

SITE CONSTRAINTS

TOWN PLANNING REGULATIONS

NOTE: TOWN PLANNING REGULATIONS ARE TO BE AMMENDED IN JANUARY 2017 - THIS DOCUMENT WILL BE REVISED ACCORDINGLY WHEN THAT INFORMATION BECOMES AVAILABLE

DENSITY ZONE	MAXIMUM PERMITTED	BUILDING LINES
Special Residential	FAR 0.35 COVERAGE 30% HEIGHT 2 storeys - 7.6 metres *above natural ground level to eaves	FRONT 7.5 metres SIDE & REAR SPACE 2.0 metres
Intermediate Residential (Medium Density Residential)	FAR N/A COVERAGE 30% HEIGHT 2 storeys - 10.6 metres *above natural ground level to ridge line	FRONT 7.5 metres SIDE & REAR SPACE 4.5metres

ADDITIONAL CONTROLS MINIMUM AREAS

PER DWELLING: minimum area for a **single dwelling** is **150sqm** excluding garages & verandahs (this applies to sites zoned **SR**)
minimum area for **MDR** sites is **80sqm** per unit excluding garage & verandahs

PARKING: **SR:** minimum single garage & one off street parking per unit
IR (MDR): minimum single garage or carport per unit & a suitable visitors parking at a rate of 1 car space for every 2 units provided that the additional car spaces are not placed on the private open area

NOTE: Relaxation of any indicated buildings lines will require consent from all the affected neighbours & the Design Review Committee of the Association

NOTE: The Design Review Committee & the Association will support the relaxation of building lines on SR sites up to 5 metres road frontage (access from bottom of site) & 3 metres road frontage (access from top of site & steep slopes)

SOFT SURFACES:

30% of the total area of the site must be comprised of "soft surfaces"

PLANTING SERVITUDES: as per *Landscape Code*

3.0metres (access from bottom of site)

2.0metres (access from top of site)

3.0metres on MDR sites (road frontage)

3.0metres on MDR sites when bordering existing neighbouring forest areas

ROOF PITCH RESTRICTIONS:

sites accessed from the bottom restricted to a roof pitch of **22 degrees or less** (steeper roof pitches are subject to approval in relation to neighbouring property heights)

DESIGN PRINCIPLES:

at least one of the "design principles" stipulated in the *Design Code* to be implemented

MDR SITES: (applicable to MDR ONLY)

Massing - cluster or "village-like" massing to be implemented

Hierarchy of public spaces - intergration of public & green spaces to be implemented





fig 01: Typical diagram illustrating the SR site constraints



The following minimum area per dwelling unit shall apply:
Private Open Area - 30m²
Usable Common Open Space - 50m²
Utility Area - 15m²

fig 02: Typical diagram illustrating the MDR site constraints

SITE DEVELOPMENT LAYOUT - revised layout to be updated as soon as available



LANDSCAPE MASTERPLAN
ZULULAMI RESIDENTIAL ESTATE

fig 03: Site Development Layout

of LANDSCAPE

- Rehabilitation of forest & wetlands
- Site zoned appropriate to micro-location
 - Forest
 - Wetland
- Nature is dominant over building

of BUILDING

- Relationship between space and nature is maximised
Large openings create visual + spatial connection to outdoors

- Passive design principles are emphasized
 - Large, deep overhangs
 - Courtyards
 - Verandahs
 - Green, planted roofs
- Finishes are natural
 - Stone
 - Earth
 - Concrete
 - Timber

of EXPERIENCE

- Outdoor activities for children & adults
 - Wetland walkways & bird hides
 - Running/cycling track
 - Open-air amphitheatre
- Forest & Beach Pavilions
 - Sporting facilities

OF BUILDING_relationship between space & nature

SEAMLESS RELATIONSHIP

- Enhance spatial and visual relationship between indoors and outdoors
- Street interface layered with levels of greenery - planting servitude
- Large glazed openings onto lush landscaped gardens
- Promote outdoor coastal living
- Nature dominant over buildings
- Maximise natural light & ventilation
- Promote sustainability




fig 04: Typical diagram illustrating the principle of a seamless relationship between space & nature through large glazed openings etc.

OF BUILDING_planted "green" roofs

- Green, planted roofs allow uninterrupted views for houses above
- Increase accessible & usable space
- Natural insulation
- Promoting conservation & rehabilitation of natural surrounds
- Enhancing visually dominance of landscape




fig 05: Typical diagram illustrating the principle of planted "green" roofs

OF BUILDING_continuous surfaces

MINIMAL PALETTE OF MATERIALS

- Enhances visual architectural integrity
- Creates unified aesthetic within each individual building as well as entire estate
- Promotes spacial objects within the design
- Promotes linearity within the design
- Colour palette complimentary to natural surrounds - greys & earthtones

NATURAL MATERIAL FINISH TO RETAINING WALLS

- Retaining walls to be stone, earth or concrete - “of the earth”
OR “green” walls - vertical gardens, stepped planted retaining walls, planted loffelstein walls




fig 06: Typical diagram illustrating the principle of continuous surfaces & use of a minimal palette of materials

OF BUILDING_pasive design principles

COURTYARDS

- Maximises natural light & ventilation
- Visual link to nature through planted courtyards
- Enhances indoor outdoor relationship
- Allows for secluded living space from bad weather
- Promote cross ventilation & natural cooling

VERANDAHS

- Maximises outdoor living
- Breaks down massing of building and softens facades
- Promotes layering of spaces through variety of materials
- Protective layer to large glazed openings - shade & filtered light

APPROPRIATE ORIENTATION

- Buildings optimally orientated to maximise sea & forest views, natural light, natural ventilation & protection from bad weather
- Optimal orientation to promote flourishing of natural landscape

USE OF WATER ELEMENTS FOR NATURAL COOLING

HIGH-LEVEL WINDOWS FOR RELEASE OF HOT AIR




fig 07: Typical diagram illustrating the principle of a “green” courtyard space

The *Design Code* is ideally suited for architects to respond positively to limit energy wastage and to reduce a generally negative impact on the environment. Notwithstanding the relevant legislative restrictions contained within the Building Control Act and in particular **SANS 10400 XA “Environmentally Sustainability and Energy Usage in Buildings”** and **“SANS 204 Energy Efficiency in Buildings”** to which architects are required to respond, *the Association* requires that all designs offer a comprehensive design solution that embraces elements of sustainable design as much as possible.

Through the encouraged implementation of sustainable principles below:

- Nature/landscape dominant over building
- Planted courtyards
- Use of water elements ie. ponds/reflection pools to promote natural cooling from prevailing winds
- Environmental control through louvred pergolas & screens
- 80% of internal spaces to have effective cross ventilation (design to avoid use of airconditioning) to promote natural heating & cooling
- Planted roofs - entire or portion of roof (encouraged roof option)
- Large overhangs
- Highlevel windows to promote release of hot air
- Thick walls on west facades & deep recesses
- Maximize natural light - larged glazed panels, skylights, dormer windows, clerestorey windows/glazed gable ends
- Alternative water heating systems - solar or heat exchangers
- Grey water systems used for garden irrigation
- Rainwater harvesting (underground water tanks preferred) - positions to be indicated on drawings
- Energy efficient appliances & LED lighting
- Solar panels - avoid being visible from the street (positioning to be flush with roof & to be approved by *Design Review Committee*)

NOTE: Each application must indicate its sustainable approach in addressing the principles above. A brief design analysis is to be submitted with each application.

SPECIFIC EXCLUSIONS

- Boxed in eaves
- Fibre cement or clay roof tiles
- Large expanse of one roof form discouraged
- Hipped roof forms (including Dutch hipped, stepped hipped, cranked)
- Mansard or Gambrel roof forms
- Porte cochere
- Thatched roofs
- No unpainted or reflective materials
- Any colour other than those approved

WALLS

SPECIFIC EXCLUSIONS

- Artificial cladding
- Corner quoins, crenellations & rustification
- Exterior arches
- Facebrick/exposed brickwork
- Highly reflective surfaces
- Ornate mouldings, surrounds or bands around openings
- Plaster techniques
- Stylized columns
- Uninterrupted blank lengths exceeding 4m
- Any colour other than those permitted

GENERAL INCLUSIONS

- Flat roof or planted roofs
- Flat roofs (if not planted) to be covered with stone chips/shards of slate (charcoal grey colour)
- Gable ends roof forms (glazed or enclosed)
- Monopitched & pitched roof forms at min. pitch **5 degrees**
- Pitched roof forms at max. pitch **35 degrees (max. width of building 7metres & subject to approval by DRC)**
- Large overhangs (min **600mm**)
- Verandahs
- Gutters - powdercoated to match roof colour (concealed gutters preferred)
- Concealed downpipes encouraged
- Rainwater goods sympathetic to wall colour
- Kliplok/Saflok, Rheinzink or similar approved profile (preferred profiles)
- S-profile/corrugated sheeting
- Same pitch skylights

NOTE: all sites accessed from the bottom are restricted to a roof pitch of 22 degrees or less (steeper roof pitches in relation to neighbouring property heights & views are subject to approval at the discretion of the *Design Review Committee*)

NOTE: All roofs to comply with SANS 10400_L & SANS XA

GENERAL INCLUSIONS

- Walls as continuous elements (application of materials) & forms encouraged
- Accepted finishes include off-shutter concrete, timber cladding, nutec cladding, brick smooth plastered, bagwash plaster
- “Green” feature walls/planted walls
- Breeze block (specific implementation on approval of aesthetics committee)
- Subterranean natural rock/stone walls (loose packed)
- Rammed-earth walls (feature wall or element ie. NOT entire house)

NOTE: All walls to comply with SANS 10400_K

SPECIFIC EXCLUSIONS

- Arched windows
- Burglar bars
- Cottage pane
- Circular or triangular windows
- Glass blocks
- HW timber - yellow or red tinted stains
- Plaster surrounds/bands
- Ornate mouldings & surrounds
- Tinted, reflective or coloured glass
- Any material or colour other than those approved

VERANDAHS, DECKS & PERGOLAS

SPECIFIC EXCLUSIONS

- Decorative columns
- Precast concrete columns
- Solid enclosure (including glass) of any verandah or patio
- Proprietary awning structures, retractable or fixed
- Attached frame verandahs or balconies
- Rustic log or gumpole construction
- Shade cloth
- “Intingus” or latte
- Stained decking - yellow or red tinted stains
- “Broekie lace” or any excessive adornment

GENERAL INCLUSIONS

- Large glazed openings encouraged
- Square or rectangular openings & shall compliment each other in design & proportion
- Concealed sliding doors encouraged
- Pivot doors (glazed or HW timber)
- HW timber louvres screens are encouraged
- HW timber shutters
- Powdercoated aluminium. See approved colours.
- HW timber - natural or painted

NOTE: All doors & windows to comply with SANS 10400_N & XA

GENERAL INCLUSIONS

VERANDAHS

- verandahs or “verandah-type” spaces encouraged to promote indoor outdoor link
- Sliding or fixed timber louvred screens to protect from prevailing winds encouraged

DECKS

- Natural (left to weather naturally) balau decking preferred
- Varied deck levels encouraged - stepped ballustrades, sunken firepit/seating areas, planters, cut outs in decking for trees & planting etc.

PERGOLAS

- Timber posts (lightweight)
- Timber louvred pergolas encouraged - left to weather naturally preferred
- Lightweight steel structure pergolas (painted to match or compliment the overall design)
- Planted pergolas & screens are encouraged

BALUSTRADES

SPECIFIC EXCLUSIONS

- Decorative metal/wrought iron
- Polished stainless steel
- Solid brick balustrades on ground level
- Resin balustrades

GARAGES & CARPORTS

SPECIFIC EXCLUSIONS

- Metal doors (**only allowed if approved**)
- Fibreglass doors (**only allowed if approved**)
- Steel framed shadeports & temporary carports




fig 08: Typical diagram illustrating garage door perpendicular to the road

GENERAL INCLUSIONS

- Stepped balustrades encouraged
- Glass balustrades
- Planters as “balustrades”
- Visually “lightweight” balustrades encouraged

NOTE: All balustrades to comply with SANS 10400_D

NOTE: All balustrade designs are subject to approval by the *Design Review Committee*

GENERAL INCLUSIONS

- Garage doors may not face the street unless treated as a continuous element (see fig.08 & fig.09) through use of cladding
- Horizontal slatted hardwood natural timber or painted timber doors (preferred)
- Carports to be treated as a detailed pergola complimenting the overall design

NOTE: Garage doors may face the internal roads within the MDR sites but NOT the estates main roads

NOTE: Boats, caravans, camper vans, motor cycles and quad bikes, or any trailer must be screened from view




fig 09: Typical diagram illustrating garage door concealed with timber cladding as a continuous element

DRIVEWAYS

SPECIFIC EXCLUSIONS

- Tarmac (asphalt) driveways
- Concrete driveways
- Gravel

BOUNDARIES, RETAINING WALLS & COURTYARDS

SPECIFIC EXCLUSIONS

- No boundary walls or fences to road frontage
- No boundary fences (only allowed if approved ie. around swimming pools & for the confinement of pets etc. must be within building lines)
- Artificial cladding or materials to walls




fig 10: Typical diagram illustrating stepped retaining wall & site constraints (site access from bottom of site)

GENERAL INCLUSIONS

- Only one driveway access per site
- Driveway entrance to be **90 degrees** with the road frontage. The driveway width over the verge and services must not exceed **3.5metres** on a SR site & **5.0metres** on a MDR site
- Driveway entrance gradient from the edge of the road up to the site boundary must be **1:6 gradient**
- Driveway gradient not to exceed **1:6** for the first **10metres** inside the property
- Driveways may only be paved with **SMARTSTONE** paduan pavers, concrete grass pavers or cobblestone or other approved
approved colour: **Charcoal ONLY** (*herringbone* pattern preferred)


GENERAL INCLUSIONS

COURTYARDS

- Planted courtyards encouraged
- Courtyard/front wall set back & not exceeding **1.8m height** (if applicable to design)
- Timber screen walls encouraged
- Screen planting between properties
- **Clear View type fencing** or other **mesh type fencing** on approval allowed within building lines on side & rear boundaries - Colour *black*

RETAINING WALLS

- Drystack retaining walls (natural rock)
- Terraced retaining walls with planting (see fig.10)
- Planted hollow drystack retaining wall - see approved plant list in *Landscape Code* - only when appropriate orientation & specified plant types
- Maximum retaining wall height of **2000mm**
- Gabion walls (use of locally sourced rock)



*principle of equal cut & fill relative to the overall length & width of specific site

fig 11: Typical diagram illustrating cut & fill principle

EXTERNAL LIGHTING

SPECIFIC EXCLUSIONS

- Any external lighting that may cause a nuisance to any neighbouring properties, or is hazardous and blinding to any motorist in any road
- Any permanent “decorative type”, “fairy lights” or festive season lights (may only be displayed for a **period of 30 days**)
- any other lighting not listed in specific inclusions
- street lights covered by cardboard, shade cloth, or any other materials as a deflector
- Lollipop or victorian type lamps and high lights, or any other lights considered offensive or a danger to road traffic and pedestrians
- harsh floodlights or uplighting (unless otherwise approved by the *Design Review Committee & the Association*)
- Coloured lighting
- Excessive light pollution

GENERAL INCLUSIONS

- Exterior lighting of buildings and building elements is permitted on application to the *Design Review Committee & the Association*
- Undergrowth/landscaping lighting is permitted on application to the *Design Review Committee & the Association*
- Solar powered lighting
- Ambient type downlighting encouraged
 - bollard type lighting not higher than **500mm**
 - undergrowth tree lighting on application

SWIMMING POOLS & WATER FEATURES

- The owner of any site which contains a swimming pool shall ensure by means of a wall or fence that no person can have access to such pool from any street or public place or any adjoining site other than through a self-closing & self-latching gate with provision for locking in such wall or fence :
- Provided that where any building forms part of such wall or fence, access may be through such building.
- Such wall or fence and any such gate shall be not less than **1.2m high** measured from ground level, and shall not contain any opening which will permit the passage of a **100mm** diameter ball.

SIGNAGE

- All sites must have a **lot/erf number** displayed during pre-construction and construction phases.
- All sites must have a **street address number** displayed which must be clearly visible and readable from the road
- The **street number** must be installed on completion of the project and prior to occupation of the building
- All **street numbers and signage** details MUST comply with the signage design of the Estate.
- In the case of a **Medium Density Residential Development (MDR)**, the name of the complex and street address number must be displayed at the entrance to the complex, and each individual unit must have a unit number displayed at each entrance to such unit. The entrance feature signage and street address details must be submitted together with the building plans to the *Design Review Committee & the Association* for approval.

NOTE: The Estate's approved signage design & related information can be obtained from *the Association Office*.

- **Swimming pools & water features are acceptable with the provisions that:**
 - _Swimming pools are permitted provided that they are constructed below ground level or terrace level
 - _above ground pools are to be clearly described; subject to approval by the *Design Review Committee*.
 - _natural/eco pools are permitted
 - _swimming pools & filtration plants to be housed within building lines
 - _discharge pipes from swimming pools must discharge water directly, via a piped system, into the regulated sewer system

NOTE: All swimming pool enclosures to comply with SANS 10400-D

NOTE: All swimming pool designs are subject to approval by the *Design Review Committee*

SERVICES

All services are to be concealed (from view from the main road), including:

- **Air conditioning units/HP condensor units and piping** (wall mounted units should be hidden from neighbours and general view and to be positioned so as not to cause noise for neighbours)
- **Gas bottles** to be housed in suitably **ventilated enclosures**
- **Geysers & heat pumps** must be **concealed** within the roof space (or building structure)
- Stand-by **generators** will be permitted in response to the electrical outages being experienced without prior warning on the following basis :
 - **Generator** must be situated in a sound proofed basement, which must also provide for access to supply the fuel for the generator within the original footprint applicable to the site.
 - Noise levels may not exceed **60 dB**, measured at a distance of **7 metres** from the generator. **60 decibels** is evaluated and equivalent to quiet conversation. The required sound level shall be recorded both in the basement and externally immediately adjacent to the basement where the generator is housed.

STORM WATER CONTROL_on site SW Policy

The **stormwater drainage system** in the Estate has been designed to the requirements of the Kwadukuza Municipality. The developers and residents of the Estate must ensure that all runoff from hardened areas is properly directed to this system.

- The soils within the Estate are **highly erodible sandy soils** and this must be considered when addressing on site Stormwater control.
It is a requirement of the development that **each site** must prepare its own **Stormwater Management Plan** and have its own **Stormwater Attenuation Tank (SAT)**. The **Stormwater Management Plan** must be submitted along with the Architects submission drawings in the form of a drawing prepared by a Registered Professional Engineer identifying Stormwater Control during and after construction. All concentrated flow from the site is to be detained in the **SAT**. The **SAT** will form part of the Stormwater Management plan for each site.
- all **runoff from grassed areas** which may concentrate against a boundary fence or similar obstruction must also be **directed to the municipal system**, via the SAT or must be spread such that the discharge does not create erosion downstream from the point of discharge.
- The **SAT** that will accept the stormwater runoff from the site and attenuate the flow of a 1 in 50 year storm to that expected during a 1 in 10 year storm.

- **Solar heating panels/photovoltaic panels** should be flush mounted against roof structures and their positions shown on drawings (for approval by the *Design Review Committee & the Association*)
- **Satellite dishes** are to be **positioned discreetly & not to be visible** from the road
 - may not be mounted on chimneys or masts
 - may be concealed in roof spaces
 - No Tv aerials may project above the ridge line of the roof
- **Swimming pool & water feature filtration plants** (to be housed and placed to minimise disturbance to neighbours)
- All **waste pipes** are to be **concealed** within walls, ducts or service yards - may not be exposed to the exterior
- **Washing lines, kitchen yard areas** are to be **concealed** behind a screened wall
- **Waste bins** are to be **concealed** in animal-proof enclosures (“wheelie” type waste bins are encouraged)

- The **SAT** is also intended to function as a silt trap and must be in place prior to any other construction work taking place on the site.
- The stormwater entering into the **SAT** should discharge into the chamber furthest from the stormwater manhole that the discharge pipe will tie into. Particular care must be taken to ensure that silt is cleaned from the chambers as often as is necessary to keep the system functioning. In this regard it will be the property owner’s responsibility to ensure that this occurs, to the satisfaction of the Local Authority and the Estate Manager.
- It is the **Owners/Developers** responsibility to employ a competent **Professional Engineer** to design the **stormwater management plan and SAT** appropriate for the construction activities to be undertaken on the site. Such system must however be able to function in the manner that the above principles provide for and must be certified as such by the Engineer.

NOTE: No development will be permitted on any site unless such a system has been designed for and constructed in accordance with the above guidelines and in accordance with the SWMP.

COLOUR PALETTE

SPECIFIC INCLUSIONS

- Roof covering to be shades of medium grey to dark charcoal grey. **Roof colour samples must be submitted to the *Design Review Committee* for approval prior to placing orders and installation**
- Fascias and bargeboards to match the main roof colour. White fascias & bargeboards without a roof colour trim will not be approved
- Rainwater goods to match or compliment the main roof colour
- Roof structure (exposed) to be **natural timber**. Or, any of the specified roof covering colours to match, or compliment the colour of the roof.
- Verandah structure & pergolas to be **natural HW timber**, or **galvanised steel** (painted any of the specified roof colours to match, or compliment the roof).
- External walls to be any of the approved colours as per the colour palette specified in this manual or on display at the Association Office.
- All colours to be “brand” specified on all drawings submitted for approval to the *Design Review Committee & the Association*.
- HW windows and doors can be **painted** or **natural**. All aluminium windows & doors as per the colour palette specified.
- Shutter and screens to be **natural HW timber** (left to weather naturally preferred)
- Timber cladding to be **natural HW timber** (left to weather naturally preferred) or painted as per the colour palette specified.
- Painted **Nutec cladding** (vertical cladding preferred)

NOTE: ALL COLOURS MUST BE SPECIFIED ON ALL DRAWINGS

APPROVED COLOURS

ROOF

- COLORPLUS *Raincloud or Slate*
- COLORBOND *Cape Charcoal, Armour Grey or Volcanic Grey*
- CHROMADEK *Dove Grey or Dark Dolphin*
- HULAMIN *Hazy Grey, Corporate Grey or Storm Grey*

NOTE: SAMPLES OF METAL ROOF SHEETS MUST BE SUBMITTED TO DESIGN REVIEW COMMITTEE FOR COLOUR APPROVAL PRIOR TO PLACING ORDER AND INSTALLATION. METAL ROOF COLOUR VARIES FROM MANUFACTURER TO MANUFACTURER

WINDOWS AND DOORS (Aluminium)

- *Matt Dark Umber Grey*
- *Matt Slate Black*
- *Matt Stone Grey*
- *Matt N.M Bronze*
- *Matt Onyx*
- *Matt Slate Black*
- *Matt New Silver*

SPECIFIC EXCLUSIONS

- **ANY COLOUR NOT SPECIFIED UNDER SPECIFIC INCLUSIONS & APPROVED COLOURS** (colours of a similar hue not included in the approved list can be submitted to the *Design Review Committee* for approval)

GARAGE DOORS

- Colours to match colour of the walls
OR entire garage facade clad as continuous element (as illustrated in fig.09)

PERGOLAS

- natural HW timber left to weather naturally preferred
- Colour to match or compliment colour of the walls from approved list

SHUTTERS & SCREENS

- natural HW timber (left weather naturally preferred)
- Colour to match or compliment colour of the walls from approved list

- Rendezvous WCEG
- Cave Grey 1IEG
- Mystique 2EEG
- Conclusion 4EEG
- Hemp 4AEG
- Topple 1CEG
- Jewel 2ADP
- Kettle Spout 1JDP
- Weave 1CN
- My Love 2GEG
- Peppercorn 2JEG
- Eclair 4CDP
- Slate of Greys 3JEG
- Cosmos 3GEG
- Karroo Sand 1HEG
- Somewhere in Between 3EEG
- Incense Bundle 3HEG
- Workshop 3IEG

PLASCON

- Dark Onyx 42
- Aluminium Snow 45
- Mandarin Tusk 49
- Off Shore 50
- Geneva Morn 51
- Crete Shore 52
- Nomadic Dream 56
- Storms Grey 58
- Addo Skin 59
- Beijing Moon 63
- Light Stone 68
- Ewa 72

- Teddy Bear Brown 1JEG
- Front Door 1HDP
- High Noon 1IDP
- Stardust 3DEG
- Great Idea 3AEG
- Karma 2HCP
- Sugars 2ICP
- Linseed 4FN
- Mouldy Granite 1HN
- Friday 1GCP
- Sixth Sense 1HCP
- Grey Dawn 2BW
- Dolomite 4CN

DULUX

- Forest Black 30YY10/038
- Mansard Stone 30YY 20/029
- Grey Tweed 30YY 22/059
- Ominous 50YR 26/023
- Midnight Hour 50 YR 13/032
- Cliffside 50 YR 38/017
- Roma Haze 10YY 54/034
- Arrow Wood 10YY 27/060
- Plateau Grey 40YY 20/081
- Wood Smoke 40YY 41/054
- Loam 50YY 12/095
- Aged Stucco 70YY 46/053
- Pendulum 30GY 10/048
- Grey Tabby 00NN 16/000
- Seal Grey 00NN 25/000
- Obsidium Glass 00NN 13/000
- Slippery Rock 90YY 28/067
- Midnite Hour 50YR 13/032
- Wet Granite 30RR 22/031
- Fog Grey 50RR 32/029

LANDSCAPING RECOMMENDATIONS

OUR AIM IS TO REHABILITATE THE INDIGENOUS VEGETATION & PROMOTE ITS USE WITHIN THE PRIVATE ERVEN, SO AS TO ENHANCE THE NATURAL BEAUTY OF THE AREA & PROVIDE HABITAT FOR LOCAL BIRDS & OTHER FAUNA ON THE ESTATE

- All architectural plan review submissions must be accompanied by a detailed landscape plan.
- All landscape plans must comply with the *Zululami Environmental Management Plan & Landscape Code* available from *the Association Office*.
- No landscaping may proceed without the written consent & approval from *the Association*.
- All landscaping must be installed by an Association approved landscaping contractor.

NOTE: SEE *LANDSCAPE CODE* FOR SPECIFIC GUIDELINES & APPROVED PLANT SPECIES LIST

REVIEW SUBMISSION PROCEDURE

ZULULAMI PANEL OF ARCHITECTS

Only pre-approved architects on the Zululami panel may submit plans to the *Design Review Committee* for review following the specified procedures & format as set out in the clauses below.

NOTE: IT IS ENCOURAGED TO MAKE USE OF THE APPROVED ARCHITECTS AS TO ENSURE THE ENVISIONED ARCHITECTURAL AESTHETIC AND MAINTAIN A HIGH LEVEL OF EXCELLENCE IN DESIGN ON THE ESTATE.

USE OF ARCHITECTS NOT ON THE PANEL

- Should an Owner wish to use an Architect not on the Zululami panel of Architects - they are required to submit their architect's CV/portfolio (in the form of a link to their website) to the *Design Review Committee* for review. The relevant CV/portfolio will then be assessed, and if considered acceptable, the architect will be placed on the panel. The architect will be given a comprehensive briefing on the *Design Code*.
- Should the architect NOT be accepted at this stage, they will not be allowed to accept the commission.
- Should an Owner/s submit a CV/portfolio of an architect they wish to use - a *Review Fee* of **R5 000 + R700 (VAT) = R5 700** will be charged to the Owner/s for the CV/portfolio to be considered.
- Should the architect be approved, the architect will be required to attend an orientation meeting on site for briefing by the *Design Review Committee*

**NOTE: ALL ARCHITECTS TO BE REGISTERED WITH SACAP as a
"PROFESSIONAL ARCHITECT"
NO TECHNICIANS OR DRAUGHTSMEN PERMITTED TO WORK ON THE
ESTATE (even if SACAP registered)**

LIST OF APPROVED ARCHITECTS

Below are listed the approved architects for the Estate. This panel has been chosen on account of the calibre of work that they produce and their suitability to carry out the envisioned aesthetic of the Estate.

The architects who make up our panel at present are:

- **Lisa Rorich Architects**

lisa@lrarchitect.co.za
031 312 0411

Designers of the Gatehouse, Offices & Clubhouse facility

- **BLOC Architects**

brandon@bloc.archi
031 566 3320

- **Ferguson Architects**

helen@fergusonarchitects.co.za
031 5647984

- **MAP Architects**

jarryd@mapgroup.co.za
032 946 3853

- **Paul Nel Architects**

studio@paulnelarchitects.com
031 313 1230

- **Rutherford Architects**

julia@rutherfordarchitect.co.za
073 217 3141

- **TC Design Group (Pty) Ltd**

philip@tcdesign.co.za
031 502 3625

- **Wyatt & Baker**

derry@wyattbaker.co.za; mike@wyattbaker.co.za
082 378 2278

- **ZAARC**

office@zaarc.co.za/ vageli@zaarc.co.za
031 569 2041

RULES APPLICABLE TO ALL ARCHITECTS WORKING ON THE ESTATE

- It is **solely the responsibility of the Owner** to enquire as to the status of the practitioner prior to commissioning them. They **MUST** be qualified architects registered with the **Institute of Architects of South Africa (SACAP)**. Technicians/draughtsmen will not be allowed to work on the estate (even if SACAP registered)
- The *Design Review Committee* will not be responsible for monies wasted on “professionals” who are not authorised to work on the estate.
- The architect **MUST** be engaged for a minimum service of design, Local Authority submission drawings and construction drawings (**Stages 1 - 4.2** as classified by SACAP). **NOTE: However it is recommended that Architects be commissioned for a full service.**
- should the architect be **appointed for a limited service** - the Owner will not deviate from the approved plans without prior input from his architect, and that deviation plans will be submitted to the *Design Review Committee* for approval before the work is implemented on site. **The Owner takes full responsibility for the changes undertaken during construction.**
- A **motivation letter** is required to be submitted to *the Association* regarding the client managing the project or appointment of a professional Project Manager.
- All architects accepting a commission on the Estate will be required to sign a document with *the Association* prior to the commencement of the commission. **The conditions will require acceptance of the following:**
 - the architect accepts the current rules pertaining to all architects on the Estate;
 - the architect accepts that the estate’s review submission procedures and documentation requirements will be strictly adhered to, failing which the architect will pay a financial penalty, the amount of which will be determined by the *Design Review Committee*;
 - the architect accepts that should plans be submitted more than **three times** for review, that a re-submission fee of **R1 204 + R196 (VAT) = R1 400** will be charged per submission;
- Architects not producing buildings of consistently high calibre may at the sole discretion of *the Association* can be removed from the “Approved Panel”
- **The Association** will inspect progress on site & sign off the buildings upon completion, thereby certifying that they have been built in accordance with the approved plans
- **Minor deviations** to the approved plan (ie. moving a single window) to be approved by *the Association* prior to the change

- **Major deviations** made to homes during construction need to be submitted as deviation plans for approval by the *Design Review Committee* at the fee stipulated. Plans submitted after the construction of deviations, and without the approval of the *Design Review Committee*, will be charged a penalty fine and may not be approved.

NOTE: ONCE THE DEVIATION HAS BEEN BROUGHT TO THE ATTENTION OF THE ASSOCIATION, IT IS AT HIS/HER DISCRETION WHETHER A CHANGE IS CLASSIFIED AS “MINOR” OR “MAJOR”

NOTE: This document is attached to the “DESIGN REVIEW COMMITTEE – PLAN SUBMISSION CHECKLIST”, and is to be signed by the architect & Owner

FORMAT OF REVIEW SUBMISSION (applicable to SR & MDR sites)

The review procedure consists of two stages aiming to avoid unnecessary time & cost delays. The preliminary plans & models will be examined at the *Design Review Committee* meeting for an “approval in principle”:

STAGE ONE - PRELIMINARY REVIEW SUBMISSION (CONCEPTUAL)

- **A3 format bound review submission document** (format template to be obtained from the Association Office)
- 2 copies of each

- **Locality plan** - google earth image with SDP overlay showing Erf location & site access from municipal road as well as all relevant cadastral, owner & architects information

- **Site layout/analysis (specific survey drawing from a registered Land Surveyor reflecting the contours of the site, boundary pegs & levels)**

- illustrating design principles implemented, site constraints, relationship to adjacent sites, buildings (if built) & road, building footprint, 30% soft surfaces, hard surfaces, driveway, retaining walls, orientation & prevailing weather etc.

- **A 3D site massing computer model** - illustrating extent of cut & fill, all retaining walls (position & type of retaining system), platform levels, natural embankments etc.

NOTE: a 3D computer massing model of development compulsory for MDR sites.

- **minimum of two 3D views** - illustrating true colours, materials & massing of adjoining sites

- **1:100 Freehand (accurate) or formal drawings illustrating the following:**

- Floorplan
- Streetscape elevation

- **Sustainable approach/es** - a brief analysis stating approach etc.

- **Mood board** - inspiration, colours & materials

- **Email to the Estate Manager a site layout plan in digital format (pdf or jpeg).**

This is to reflect the boundary of the site, the building footprint, the 30% soft surfaces area and driveway.

- **UNDERTAKING: The architect is to list any deviations from the guidelines. If such a list is not given and the plans are approved, with deviations being later discovered, the author is responsible for rectifying the deviations and any cost incurred by the Design Review Committee. The Design Review Committee has the right to revoke approval if deviations are discovered.**

NOTE: Attached to the end of this Design Code manual are the relevant check-lists that are to accompany the two stage plans review submission made to the Design Review Committee.

STAGE TWO - FINAL REVIEW SUBMISSION

- **A1 Format - 2 copies of each**

- **Local Authority submission plans**

- **May not deviate from Stage One approved submission**

Your final comprehensive plans for the Estate shall include the following:

- **A site development plan 1:200**

The site plan is to record amongst the normal details any servitudes which may traverse the site in respect of services. The site plan is to also show the proposed contractors yards, storage facilities and access proposal to the site etc.

- **One set of comprehensive building plans of all levels, sections and elevations (min.1:100)** as required for Local Authority Submission. Elevations are to be in full colour, indicative of the colours selected and the materials to be used. Sections are to indicate ceiling & roof levels as well as window and door descriptions.

- **All plans are to show all materials used & colours must be selected from the palette of colours as laid down in the architectural guidelines.**

- **Plans are to be in detail rather than being marked “as to clients approval”. Plans cannot be approved where detail is not provided.**

- **A landscaping plan 1:100**

The landscaping plan is to include a landscape design with a complete list of suggested plants divided into categories of indigenous trees, shrubs, ground covers, grasses and lawn types, all of which must compliment the site and comply with list of approved plants and guidelines within the *Landscape Code* provided. Please note that the Environmental Management Plan (EMP) for the Estate is to be adhered to in its entirety. A copy of the EMP is available from the Association Office.

The plan will be checked by a landscaper on the *Design Review Committee*.

- **Storm Water Management Plan (SWMP)**, to be approved by the consulting engineers to the Association and the Local Authority prior to any construction activity occurring on site. Each SWMP must be in accordance with the estate’s *SW Policy*.

- **Existing Estate Engineering Services running mid block and on roads must be clearly indicated & annotated on drawings submitted for review**

REVIEW SUBMISSION FEES

SPECIAL RESIDENTIAL UNITS:

Architects on the panel:

STAGE ONE Submission fee **R3 870 + R630 (VAT) = R4 500****STAGE TWO** Submission fee **R6 020 + R980 (VAT) = R7 000**

Architects not on the panel:

Pre-submission fee **R5 000 + R700 (VAT) = R5 700****STAGE ONE** Submission fee **R3 870 + R630 (VAT) = R4 500****STAGE TWO** Submission fee **R6 020 + R980 (VAT) = R7 000****MEDIUM DENSITY RESIDENTIAL (MDR) SITES:**

Architects on the panel:

STAGE ONE Submission fee **R5 246 + R854 (VAT) = R6 100****STAGE TWO** Submission fee **R9 460 + R1 540 (VAT) = R11 000****PLUS R1 500 + R210 (VAT) = R1 710 per unit**

Architects not on the panel:

Pre-submission fee **R5 000 + R700 (VAT) = R5 700****STAGE ONE** Submission fee **R5 246 + R854 (VAT) = R6 100****STAGE TWO** Submission fee **R9 460 + R1 540 (VAT) = R11 000****PLUS R1 500 + R210 (VAT) = R1 710 per unit**

OTHER FEES PAYABLE

SPECIAL RESIDENTIAL UNITS:Refundable Construction Deposit **R10 000 + R 1 400 (VAT) = R11 400****MEDIUM DENSITY RESIDENTIAL (MDR) SITES:**Refundable Construction Deposit **R20 000 + R 2 800 (VAT) = R22 800****SR RESUBMISSION FEES R1 204 + R196 (VAT) = R1 400 per submission****MDR RESUBMISSION FEES R1 204 + R196 (VAT) = R1 400 per submission (per unit)****NOTE: These fees are to accompany all first building plan review submissions, and are to be paid directly into the following account:**

Account Name:

Account Number:

Held at:

Branch Code:

**Kindly fax a copy of the deposit slip to on fax number:
or email to**

REVIEW SUBMISSION DATES

The plans must be submitted to *the Association* by **14 days** prior to the provided meeting date, and will be reviewed the day thereafter for admittance onto the Agenda of the *Design Review Committee*. Plans not complying with the requirements will be given notification hereof and will be allowed **48 hours** in which to make the necessary amendments or additions thereto, failing which they will not be admitted onto the Agenda and will have to wait until the following meeting for admittance and scrutiny.

The *Design Review Committee* will meet at least once a month and such dates will be published by *the Association*. Dates may be slightly flexible to accommodate members of the *Design Review Committee*.

The Association shall have up to **14 days** from the date of the review submission meeting to provide you with comments and/or the status of your plans approval etc.

All communications regarding the submission and approval of plans is to be done through at the Estate’s Association Office and NOT with the *Design Review Committee* members.

..... contact details are as follows:

Tel:

Fax:

Email:

NOTE: THE DECISION OF THE DESIGN REVIEW COMMITTEE IS FINAL

LOCAL AUTHORITY SUBMISSION

Following approval by the *Design Review Committee*, plans must be submitted to the Local Authority as per the standard required submission procedures to obtain planning approval prior to commencement of construction.

NOTE: The Local Authority will not scrutinize any drawings without the ESTATE'S approved stamp.

NOTE: the controls of this building design code do not override those of the Local Authority. Both the drawings approved by the *Design Review Committee* or *the Association* and the Local Authority are to be reflected on the working drawings/construction drawings. A compulsory site handover meeting must take place with a representative of the Association prior to any site work commencing.

COMMENCEMENT OF CONSTRUCTION

BUILDING PERIOD

In terms of the Contract of Sale and Title Deed on freehold sites (SR):

- The Purchaser shall within a period of **36 (thirty six) months** from the Date of Transfer have commenced the construction of the Dwelling on the Property with a minimum floor area of **150 (one hundred and fifty) m²** (excluding garages and verandahs).
- The Purchaser shall within a period of **54 (fifty four) months** from the Date of Transfer have completed the construction of the Dwelling on the Property with a minimum floor area of **150 (one hundred and fifty) m²** (excluding garages and verandahs).

In terms of the Contract of Sale and Title Deed on Medium Density Residential sites (MDR):

- The Purchaser shall within a period of **6 (six) years** from the Date of Transfer have completed the construction all the Dwelling Units on the Property with a minimum floor area of **80 (eighty) m² PER UNIT** (excluding garages and verandahs).
- Should all the Dwelling Units not have been constructed on the Property within a period of **6 (six) years** of Date of Transfer of the Property to the Purchaser, the Purchaser shall pay to the Seller the sum of **R1 000,00 (one thousand rand)** plus VAT per month, per undeveloped Dwelling Unit until the Dwelling Units are completed.

The Contractor is to be NHBRC registered.

BUILDING CONSTRUCTION - GENERAL

Prior to the commencement of construction the following conditions are to have been fulfilled:

- Prior to commencement of construction a fully refundable deposit shall be payable as stipulated within the fees payable listed on page 22. The *Design Review Committee* is entitled to access the site for the full duration of the contract period.
- **The building deposit will be retained until the building is complete and an inspection has been undertaken by the Association Office to confirm the following:**
 - That the building has been built in accordance with the approved plan and/or that the deviation plans have been approved and the house built in accordance with these;
 - That the roads, verges, services, kiosks etc have not been damaged during the construction process. If they have been then these monies will be used for the rectification thereof.
 - That there are no outstanding fines due by the contractor. If these have not been paid then they will be deducted off the building deposit.

NOTE: Should the above found to be in order then the building deposit will be returned to the Owner.

- Prior to construction activity occurring on site, a **Storm Water Management Plan (SWMP)** must have been approved by *the Association*/consulting engineers and the Local Authority.

- Please note that an **On-Site Storm Water Attenuation System** must be an integral component of the site's **Storm Water Management System** and must be constructed as one of the first construction activities in accordance with the Estate's *SW Policy*.

- Construction on site may only commence once you are in receipt of a letter from the Local Authority granting you permission for early commencement in accordance with the stipulated rules & regulations by the Local Authority. Alternatively (& preferably) your plans are to have been approved by the Local Authority and a letter is to be provided to this effect.

A copy of either of these letters is to be provided to *the Association* prior to the commencement of construction.

- The landscaping plan **MUST** be approved prior to construction commencing.
- The Contractor is to have been briefed and have accepted the terms and conditions of this document.

Once approval has been obtained, site camp is to be set up as follows:

- The site is to be totally **enclosed with an 80% factor dark green shade cloth, 1.8m high with a single access and egress gate at a single point entry** to be determined and agreed between the Association and the builder / architect / owner. **The external battens are to be painted dark green. This is to be maintained to a high standard at all times.**

By way of shade cloth, Bulk Fence provide a "*Shademesh Fencing*", a weld mesh fence incorporating 80% green shade cloth fencing. It provides a neat finish to the site and is maintenance free.

A **site board** is to be erected within **7 days** of the site handover date.

- Containers used on site are to be green or grey in colour.
- *The Association* will remove all plants from the verge prior to site establishment to permit a single access point.
- Suitable on site toilet facilities are to be provided and maintained in a hygienic condition.

- Prior to construction, it is advisable that a detailed Geotechnical Investigation be carried out on each individual site to more accurately determine the method of founding suited to the proposed structure to be developed.

- The contractor is responsible to identify and peg the position of the site and to ensure that the screening off takes place within the site area.

- Co-ordinates of peg numbers can be obtained from our land surveyor,
– contact tel:

DURING CONSTRUCTION

NOTE: Refer to the *Estate's Developers and Contractors Protocol*.

SITE DEVELOPMENT PLAN (compulsory for ALL MDR sites)

Notwithstanding the provision of the relevant Town Planning Scheme, the owner or developer of any land shall not develop any Lot, Erf, Site, or Curtilage within the area of the scheme, whether in part or in whole, without the written approval of a Site Development Plan, which plan shall be submitted where it is in the opinion of the Local Authority that it is necessary to do so as a consequence of unique characteristics or circumstances which may pertain to the land concerned, or where the development proposed is of a medium density housing, sectional title, share block or multi-unit nature.

FOR THE PURPOSES OF SECURING THE APPROVAL OF A SDP IN TERMS OF THE PROVISIONS OF THE KWADUKUZA TOWN PLANNING SCHEME IN COURSE OF PREPARATION, THE APPLICANT SHALL SUBMIT THE FOLLOWING:

- 1)
 - i. **A layout plan or plans showing, where applicable:**
 - a) The position, dimensions and materials to be used in the construction of all roads, drive-ways, parking areas, squares and pedestrian access ways, if any;
 - b) The boundaries of all dwelling unit cartilages, private open areas and common open spaces;
 - c) The position, nature, extent and levels of all proposed and existing buildings on the site and adjoining sites;
 - d) The proposed landscaping of the site;
 - e) The proposed public open space;
 - f) The position and nature of recreation facilities, if any;
 - g) The position and extent of all utility areas.
 - ii. A set of sketch drawings prepared by an architect at a scale of 1 : 100 showing the plans, sections and elevation of each type of structure within the proposed development and particulars of the materials and colours to be used for the exterior wall finishes and roof or roofs; together with both front and rear elevations of each typical group of dwelling units at a scale of 1 : 100 or 1 : 200;
 - iii. **A table indicating:**
 - a) The total area of the site;
 - b) The total number of dwelling units;
 - c) The total floor area;
 - d) The total number of car parking spaces provided for visitors and for residents;
 - e) The extent of the usable common land, the smallest private open area, the smallest dwelling unit cartilage and the smallest utility area;
 - f) **The areas of public open space and other public uses where applicable;** and
 - iv. Any other documents which the Local Authority may reasonably require.
- 2) (i) The following minimum areas per dwelling unit shall apply to a **Medium Density Housing** site:
 - a) **Private Open Area – 30 m²**
 - b) **Usable Common Open Space – 50m²**
 - c) **Utility Area – 15 m²**
- ii The minimum floor area of a garage or carport shall be 21 m², with a minimum width of 3,5m².

- 3)
 - i. Where in the opinion of the Local Authority a road within a **Medium Density Housing site** should serve the public, the Local Authority may require the road to be registered as a public road, provided that for the purpose of bulk and coverage calculation, the area of the public road shall be included in the gross site area.
 - ii. The **minimum width** of a road carriageway within a **Medium Density Housing site** shall be **3 metres** where the carriageway is one-way and **5,5 metres** where the carriageway is two-way.
 - iii. Situated at the end of every cul-de-sac there shall be provided turning space to the satisfaction of the Local Authority.
 - 4) In the event of the different dwelling unit cartilages being transferred in freehold or registered leasehold title, the Local Authority shall require that:-
 - i. (a) the common land shall be owned exclusively by the freehold or registered leasehold owners of the dwelling units in co-ownership; and
 - (b) no co-owners shall be entitled to require the partition of the common land according to the proportion of his share;
 - ii. A Home Owners' Association shall be established. Such Association shall administer and maintain the common land, control the external appearance of buildings within the Medium Density Housing site and deal with any other matter pertaining to the Medium Density Housing site which is of common interest to its members. The affairs of the Association shall be regulated by a memorandum and Articles of Association. The Memorandum and Articles of Association shall have been submitted to the Local Authority who shall have certified that it has no objection to these documents;
 - iii. No dwelling unit cartilage within the Medium Density Housing site or within any portion of the site specified by the Local Authority shall be transferred or separately registered before the whole Medium Density Housing site or the specified portion of the Medium Density Housing site within which the cartilage is situated has been developed to the satisfaction of the Local Authority.
 - 5)
 - i) Notwithstanding the requirements in 4.7 (1) and 4.7 (2) wherever it is intended to develop a site for Medium Density Housing in a Special Residential zone, the special consent of the Local Authority shall first be obtained.
 - ii. In the Special Residential zone the maximum number of dwelling units which may be established on a Medium Density Housing site shall be obtained by dividing the registered surveyed area of the property concerned by the appropriate minimum lot area per dwelling house as specified in Clause 5.2 and rounded off to the nearest whole number. Provided further that on lots of greater than 3 000m², the Board may authorize a maximum permissible density of 15 units per hectare rounded off to the nearest whole number.
 - 6)
 - i) Notwithstanding (5) (ii) above, with regard to physically difficult residential sites, the maximum number of dwelling units which may be established on a Medium Density Housing site shall be calculated in accordance with the provisions of Annexure H of this Scheme.
- NOTE: *The Association* does not submit any plans to the Local Authority on behalf of Developers or Owners. The submission of plans to the Local Authority for approval is entirely the responsibility of the appointed professional Architect and/or Principal Agent.**

ZULULAMI DESIGN CODE
CHECKLIST - SR SITES

DEVELOPMENT NAME:
Portion No:

REVIEW SUBMISSION CHECKLIST	1	2
LIST OF REQUIRED DRAWINGS - See template for Stage 1 submission		
Locality plan		
Site layout/analysis (survey drawing showing contours, boundary pegs & levels)		
3D site massing model - extent of cut & fill & retaining walls		
3D views - min. of two images illustrating true colours & materials		
Floorplan 1:100 on site plan (showing extent of site & adjoining properties)		
Streetscape elevation		
Sustainable approach - a brief analysis		
Mood board - inspiration, colours & materials		
Site Plan		
Floorplan/s		
Electrical Layout		
Elevations		
Sections		
Pool details - plan & sections including fence extent & design		
Water reticulation		
Glazing Schedule		
Landscaping plan		
Storm Water Management Plan (SWMP)		
Driveway section/details		
SITE CONSTRAINTS		
FAR - 0.35 - schedule of areas annotated		
COVERAGE - 30% - schedule of areas annotated		
FRONT BUILDING LINE 7.5metres - annotated		
SIDE BUILDING LINES 2.0metres - annotated		

REAR BUILDING LINE 2.0metres - annotated		
Height - not exceeding 7.6metres (above natural ground level to eaves) - must be annotated		
Neighbours consent for encroachment of building lines attached (if applicable)		
Single dwelling min. area of 150sqm		
Parking - minimum requirements achieved - single garage & one off street		
30% of the total area of the site must be "soft surfaces"		
Planting servitude - 3.0metres (access from bottom of site) - annotated		
Planting servitude - 2.0metres (access from top of site) - annotated		
Roof pitch of 22 degrees or less (access from bottom of site) if applicable		
At least one design principle implemented		
ROOF		
Form - pitched, gable ends, flat, mono-pitch, NO hipped or cranked		
Roof overhangs - min 600mm		
Finish - all exposed roof members to be natural or painted		
Roof covering - full annotation		
Roof covering - sample provided if not on approved list		
Pitch/es to be annotated		
Skylights - following the same pitch as roof		
Gutters - powder coated aluminium to match roof colour & concealed rwdps		
WALLS		
Wall finish/materials to be annotated		
Colours to be annotated		
DOORS & WINDOWS		
Door material, colour & texture to be annotated		

ZULULAMI DESIGN CODE
CHECKLIST - SR SITES

DEVELOPMENT NAME:
Portion No:

REVIEW SUBMISSION CHECKLIST	1	2
VERANDAHS, DECKS & PERGOLAS		
Columns & pergolas - natural timber or steel to be annotated		
BALUSTRADES		
Ballustrades - stepped ballustrade, glass or approved design		
GARAGES, CARPORTS		
Garage facing road - must be concealed as continuous element (cladding)		
Door material, colour & texture to be annotated		
Garages attached to main structure		
Garage perpendicular to road		
Carports attached to main structure		
Carports treated as detailed pergola		
DRIVEWAYS		
Only one driveway access per site & 90 degrees with road frontage		
Driveway must not exceed 3.5 metres in width		
Driveway extended to road edge		
Driveway gradient not to exceed 1:6 for the first 10metres inside property		
Services on verge indicated on plan		
Paving design layout - colour & pattern indicated		

BOUNDARIES, RETAINING WALLS & COURTYARDS		
No boundary walls or fences on road frontage boundary		
Courtyard/front wall set back & not exceeding 1.8m height		
Screen walls to be annotated & not exceeding 1.8m height		
Retaining walls to be annotated in detail - max. 2.0m height		
All retaining walls exceeding 1.0m height to be approved & specified by Engineer		
Clear View type fencing or other mesh type fencing on approval allowed within building lines on side & rear boundaries - extent & heights annotated. Colour <i>black</i>		
EXTERNAL LIGHTING		
All external lighting to be indicated		
Landscape lighting to be indicated on landscape plan		
SWIMMING POOLS		
Swimming pools & water features to be annotated including extent of fence		
Pool/water feature filtration plants to be housed & placed to minimize disturbance		
SIGNAGE		
Signage - position indicated & annotated		
SERVICES		
All waste pipes to be concealed		
AC/HP units to be concealed from neighbours & general views		
Geysers & heatpumps to be concealed within roof space		
Gas bottles to be concealed & in ventilated enclosures		
Gas bottles to be concealed & in ventilated enclosures		
Solar heating/photovoltaic panels to be flush mounted against roof structure		

ZULULAMI DESIGN CODE
CHECKLIST - SR SITES

DEVELOPMENT NAME:
Portion No:

REVIEW SUBMISSION CHECKLIST	1	2
Solar heating/photovoltaic panels to be flush mounted against roof structure		
Washing lines, kitchen & yard areas are to be concealed		
Waste bins to be concealed		
STORM WATER CONTROL		
SWMP prepared by an engineer		
Underground/concealed water tanks - annotated		
Storm water channel/cut-off drain required at driveway (for site where garage is the same level or above the road level)		
ADDITIONAL NOTES		

ZULULAMI DESIGN CODE
CHECKLIST - MDR SITES

DEVELOPMENT NAME:
Portion No:

REVIEW SUBMISSION CHECKLIST	1	2
LIST OF REQUIRED DRAWINGS - See template for Stage 1 submission		
Locality plan		
Site layout/analysis (survey drawing showing contours, boundary pegs & levels)		
3D site massing model - extent of cut & fill & retaining walls		
3D views - min. of two images illustrating true colours & materials		
3D massing model of development - cluster or "village-like" massing to be implemented & hierarchy of public spaces		
Floorplan 1:100 on site plan (showing extent of site & adjoining properties)		
Streetscape elevation - estate road/entrance to development		
Sustainable approach - a brief analysis		
Mood board - inspiration, colours & materials		
Site Development Plan		
Floorplan/s		
Electrical Layout		
Elevations		
Sections		
Pool details - plan & sections including fence extent & design		
Water reticulation		
Glazing Schedule		
Landscaping plan		
Storm Water Management Plan (SWMP)		
Driveway section/details		
Storm Water Management Plan		
Driveway section/details		

SITE CONSTRAINTS		
FAR - n/a - schedule of areas annotated		
COVERAGE - 30% - schedule of areas annotated		
FRONT BUILDING LINE 7.5metres - annotated		
SIDE BUILDING LINES 4.5metres - annotated		
REAR BUILDING LINE 4.5metres - annotated		
Height - not exceeding 10.6metres (above natural ground level to ridge line) - must be annotated		
min. area of 80sqm PER UNIT dwelling		
Parking - minimum single garage/carport per unit & suitable visitors parking at a rate of 1 car space for every 2 units provided		
30% of the total area of the site must be "soft surfaces"		
3.0metres planting servitude (road frontage)		
3.0metres planting servitude (bordering existing forest areas)		
Roof pitch of 22 degrees or less (access from bottom of site) if applicable		
At least one design principle implemented		
Massing - cluster or "village-like" massing to be implemented		
Hierarchy of public spaces - intergration of public & green spaces to be implemented		
ROOF		
Form - pitched, gable ends, flat, mono-pitch, NO hipped or cranked		
Roof overhangs - min 600mm		
Finish - all exposed roof members to be natural or painted		
Roof covering - full annotation		
Roof covering - sample provided if not on approved list		
Pitch/es to be annotated		
Skylights - following the same pitch as roof		
Gutters - powder coated aluminium to match roof colour & concealed rwdps		

ZULULAMI DESIGN CODE
CHECKLIST - MDR SITES

DEVELOPMENT NAME:
Portion No:

REVIEW SUBMISSION CHECKLIST	1	2
WALLS		
Wall finish/materials to be annotated		
Colours to be annotated		
DOORS & WINDOWS		
Door material, colour & texture to be annotated		
VERANDAHS, DECKS & PERGOLAS		
Columns & pergolas - natural timber or steel to be annotated		
BALUSTRADES		
Ballustrades - stepped ballustrade, glass or approved design		
GARAGES & CARPORTS		
Door material, colour & texture to be annotated		
Garages attached to main structure		
Carports attached to main structure		
Carports treated as detailed pergola		
DRIVEWAYS		
Only one driveway access per unit & 90 degrees with road frontage		
Driveway must not exceed 5.0 metres in width (main entry)		
Driveway extended to road edge		

Driveway gradient not to exceed 1:6 for the first 10metres inside property		
Services on verge indicated on plan		
Paving design layout - colour & pattern indicated		
BOUNDARIES, RETAINING WALLS & COURTYARDS		
No boundary walls or fences on road frontage boundary		
Courtyard/front wall set back & not exceeding 1.8m height		
Screen walls to be annotated & not exceeding 1.8m height		
Retaining walls to be annotated in detail - max. 2.0m height		
All retaining walls exceeding 1.0m height to be approved & specified by Engineer		
Clear View type fencing or other mesh type fencing on approval allowed within building lines on side & rear boundaries - extent & heights annotated Colour black		
EXTERNAL LIGHTING		
All external lighting to be indicated		
Landscape lighting to be indicated on landscape plan		
SWIMMING POOLS		
Swimming pools & water features to be annotated including extent of fence		
Pool/water feature filtration plants to be housed & placed to minimize disturbance		
SIGNAGE		
Signage - position indicated & annotated		
SERVICES		
All waste pipes to be concealed		

ZULULAMI DESIGN CODE
CHECKLIST - MDR SITES

DEVELOPMENT NAME:
Portion No:

REVIEW SUBMISSION CHECKLIST	1	2
Geysers & heatpumps to be concealed within roof space		
Gas bottles to be concealed & in ventilated enclosures		
Gas bottles to be concealed & in ventilated enclosures		
Solar heating/photovoltaic panels to be flush mounted against roof structure		
Washing lines, kitchen & yard areas are to be concealed		
Waste bins to be concealed		
STORM WATER CONTROL		
SWMP prepared by an engineer		
Underground/concealed water tanks - annotated		
Storm water channel/cut-off drain required at driveway (for site where garage is the same level or above the road level)		
ADDITIONAL NOTES		